LINCOLN CITY/LANCASTER COUNTY PLANNING STAFF REPORT

for February 4, 2004 PLANNING COMMISSION MEETING

P.A.S.: Annexation #03008, Change of Zone #04013, Special Permit #2045

PROPOSAL: To create 56 lots, annex approximately 20 acres and change the

zoning on a portion from AG, Agriculture to R-3, Residential.

LOCATION: NW 56th Street and W. Thatcher Lane.

WAIVER REQUEST:

Eliminate the preliminary plat process

Allow sanitary sewer lines to run opposite street grades

Allow the transfer of sanitary sewer from one basin to another

Allow lots to exceed the 3:1 lot depth to width ratio

Allow lots with less than the minimum required lot width

Allow lots with less than the minimum required area

LAND AREA: 20.92 acres, more or less (annexation and CUP)

Less than 1 acre (change of zone)

CONCLUSION: With conditions the proposal is in conformance with the Comprehensive

Plan, Zoning and Subdivision Ordinances.

RECOMMENDATION:

Annexation #03008
Change of Zone #04013
Approval
Special Permit #2045
Conditional Approval
Eliminate the preliminary plat process
Allow sanitary sewer lines to run opposite street grades
Allow the transfer of sanitary sewer from one basin to another
Allow lots to exceed the 3:1 lot depth to width ratio

Approval
Approval
Approval

Allow lots with less than the minimum required lot width

Approval

Allow lots with less than the minimum required area Approval

GENERAL INFORMATION:

LEGAL DESCRIPTION: See two attached legal descriptions.

EXISTING ZONING: R-3, Residential and AG, Agriculture.

EXISTING LAND USE: Farm.

SURROUNDING LAND USE AND ZONING:

North: Undeveloped R-3, Residential South: Undeveloped AG, Agriculture

East: Residential R-3 West: Undeveloped AG

HISTORY: The original sumittal (11/26/03) was for the entire 80 acre tract owned by the applicant, however, it was determined that the entire tract could not be served with either water or sanitary sewer. Therefore, the application was reduced to the eastern 20 acres, as it is now presented.

The area was zoned A-2, Single Family Dwelling District until it was updated to R-3, Residential during the **1979** zoning update. The zoning classification followed what the Public Works and Utilities Department believed could be provided with sewer, but did not reflect whether or not there was water pressure.

COMPREHENSIVE PLAN SPECIFICATIONS: This area is shown as Urban Residential in the Comprehensive Land Use Plan. (F-25)

The area is shown within the future service limit. (F-27)

Guiding Principles for New Neighborhoods indicates:

"Encourage a mix of housing types, single family, townhomes, apartments, elderly housing all within one area; Similar housing types face each other: single family faces single family, change to different use at rear of lot; Parks and open space within walking distance of all residences; Multi-family and elderly housing nearest to commercial area; Pedestrian orientation; shorter block lengths, sidewalks on both sides of all roads; Public uses (elementary schools, churches) as centers of neighborhood – shared facilities (city parks & school sites)". (F-67)

"Natural and environmentally sensitive areas should be preserved within neighborhoods. Conservation areas and open lands should be used to define and connect different neighborhoods". (F-17)

UTILITIES: Will be provided in NW 56th Street.

TOPOGRAPHY: Sloping to the middle of the plat with a drainage depression running north-south through the center of the plat. The area drains south toward Outlot B, which is the lowest point of the plat and is shown for stormwater drainage.

TRAFFIC ANALYSIS: NW 56th Street is presently a two lane gravel road. The development east of this property was required to pave NW 56th Street as part of that development. NW 56th Street is shown as an urban minor arterial. Internal streets are all local.

Page 3

A pedestrian trail is shown along Adams Street and NW 48th Street (F-95).

The boundaries of the plat are within the turning zone of the Airport Zoning Map. The Airport Zoning regulations indicate that areas within the turning zone shall not have a height in excess of 150 feet above the elevation at the closest point on the nearest runway, which is the south runway with a height of 1195.45 NAVD 1988. The applicant needs to note this on the plan.

PUBLIC SERVICE: The nearest fire station is #11, Lincoln Air Park West at 3401 NW Luke Street, approximately 1.25 miles from this site. Olympic Heights Public Park is to the northeast of this plat.

The Parks and Recreation Department determined they did not want park land dedication with this plat and opted for the collection of impact fees.

REGIONAL ISSUES: Much of this area, not including the area of the special permit, has elevations higher than can be provided with adequate water pressure for residential uses. Due to the lack of water pressure much of the land north and west of this site cannot be developed until water pressure issues are resolved.

ENVIRONMENTAL CONCERNS: The developer is preserving a stand of trees in Outlot B. The land to the north is very unique, including deep gullies and is heavily wooded for Lancaster County.

AESTHETIC CONSIDERATIONS: The preservation of existing mature trees is a wonderful asset to this project.

ANALYSIS:

- This is a request to annex approximately 20 acres and develop 56 lots. Most of the area is already zoned R-3, Residential. The developer agreed to preserve most of the existing trees by showing them in Outlot B.
- When the existing zoning line was created, the intent was to follow the ridge line to indicate the sewerable area. At the time, the technology was not detailed enough and the zoning line must be adjusted. The request for the change of zone follows the ridgeline and indicates the area which can be served with sanitary sewer. The Public Works and Utilities Department agrees with this interpretation of the contours and does not object to the request.
- 3. The developer requests waivers which are consistent with many community unit plans, including allowing lots to exceed the 3:1 lot depth to width ratio, allowing lots with less than the minimum required lot width, and allowing lots with less than the

minimum required area. Planning staff recommends approval to these waivers because they are consistent with the intent of the CUP ordinance in allowing creative methods to preserve natural features. An existing tree mass is being preserved in Outlot B.

- 4. The Public Works and Utilities Department indicated they do not oppose the waiver requests because of the following reasons: The requested waiver for running sanitary sewer opposite street grade is acceptable as it does not cause the sewer depth to be in excess of design standards. The requested waiver for transferring sewer from one basin to another is acceptable to Public Works as the Waste Water section has stated that the addition of this plat does not cause capacity problems down stream.
- 5. The Public Works and Utilities Department indicated that according to the grading and drainage plan, portions of the project are to drain to the proposed detention cell via a storm sewer system. The pipe sizing calculations shown on the grading and drainage plan do not reflect this assumption and must be revised.
- 6. The Building and Safety Department Fire Prevention/Life Safety Code section indicated the site plan is deficient in showing fire hydrants.
- 7. The Public Works and Utilities Department Watershed Management section indicated that a geotechnical engineer or a professional geologist must certify that the soil data supplied from the soil survey maps is still appropriate. If the soil survey maps are not appropriate, a subsurface investigation shall be performed and an explanation on how the soil properties will affect the development shall be submitted (26.15.020-e)

CONDITIONS for Special Permit #2045:

Site Specific:

- 1. After the applicant completes the following instructions and submits the documents and plans to the Planning Department office and the plans are found to be acceptable, the application will be scheduled on the City Council's agenda:
 - 1.1 Revise the site plan to show:

Density calculations.

Indicate the purpose of Outlots A and C.

Indicate the lot area for all lots.

Show minimum opening elevations along the drainageway.

Certification from a geotechnical engineer of the soil characteristics to the satisfaction of the Public Works and Utilities Department Watershed Management Department.

A note indicating that this area is within the airport turning zone and all construction must be in conformance with the airport zoning regulations.

Revisions to the satisfaction of the Building and Safety Fire Prevention/Life Safety Code Department.

Revisions to the grading and drainage plat to the satisfaction of the Public Works and Utilities Department.

All requested LES easements.

All required waivers in the waivers table on the site plan.

1.2 Revise the landscape plan to show:

All required screening.

Indicate trees to remain.

A note to the landscape and site plan to indicate that trees in Outlot B are to remain.

The landscape plan so that it matches the site plan layout.

Revisions as requested by the Parks and Recreation Department.

2. This approval permits 56 dwelling units and allows the following modifications: Allow sanitary sewer lines to run opposite street grades, allow the transfer of sanitary sewer from one basin to another, allow lots to exceed the 3:1 lot depth to width ratio, allow lots with less than the minimum required lot width, and allow lots with less than the minimum required lot area

Special Permit #2045 Annexation #03008

The waiver of the preliminary plat process shall only be effective for a period of ten (10) years from the date of the city's approval, and shall be of no force or effect thereafter. If any final plat on all or a portion of the approved community unit plan is submitted five (5) years or more after the approval of the community unit plan, the city may require that a new community unit plan be submitted, pursuant to all the provisions of section 26.31.015. A new community unit plan may be required if the subdivision ordinance, the design standards, or the required improvements have been amended by the city; and as a result, the community unit plan as originally approved does not comply with the amended rules and regulations.

General:

- 3. Before receiving building permits:
 - 3.1 The permittee shall have submitted a revised and reproducible final plan including 7 copies and the plans are acceptable.
 - 3.2 The construction plans shall comply with the approved plans.
 - 3.3 Final Plats shall be approved by the City.

STANDARD CONDITIONS:

- 4. The following conditions are applicable to all requests:
 - 4.1 Before occupying the dwelling units all development and construction shall have been completed in compliance with the approved plans.
 - 4.2 All privately-owned improvements shall be permanently maintained by the owner or an appropriately established homeowners association approved by the City Attorney.
 - 4.3 The site plan accompanying this permit shall be the basis for all interpretations of setbacks, yards, locations of buildings, location of parking and circulation elements, and similar matters.
 - 4.4 This resolution's terms, conditions, and requirements bind and obligate the permittee, its successors and assigns.
 - 4.5 The applicant shall sign and return the letter of acceptance to the City Clerk within 30 days following the approval of the

special permit, provided, however, said 30-day period may be extended up to six months by administrative amendment. The clerk shall file a copy of the resolution approving the special permit and the letter of acceptance with the Register of Deeds, filling fees therefor to be paid in advance by the applicant.

Prepared by:

Becky Horner, 441-6373, rhorner@ci.lincoln.ne.us
Planner

DATE: February 12, 2004

APPLICANT: Lyle Loth

ESP

601 Old Cheney Road, Suite A

Lincoln, NE 68512 (402)421-2500

OWNER: Hartland Homes, Inc.


P.O. Box 22787

Lincoln, NE 68542-2787

CONTACT: Lyle Loth

(402)421-2500

F:\FILES\PLANNING\PC\PERMITS\SP\2000\SP2045.cardinalheights2nd.rdh.wpd




Special Permit #2045 Annexation #03008 NW 56th & W. Holdrege St. Cardinal Heights 2nd Add. Zoning:

One Square Mile Sec. 13 T10N R5E







W. Adams St.

W. Holdrege St.

Highway Business District Highway Commercial District General Commercial District Indiadral District Industrial Park District Employment Center District Public Use District m-plantarcome/CO_sprep2045

R-1 to R-8Penidental District

Agricultural District Agricultural Residential District

Suburban Office District Office Park District

Construction District Lincoln Center Business District

Residential Yvansition District Local Business District

Planned Neighborhood Business District

Planned Regional Eusiness Clinicial Interstate Commercial District

Office District

Residential Convervation District

AG

0.7

0.3 R-T

B-2 B-3

8-6

AGR P.C

Lincoln City - Lancaster County Planning Dept.



Change of Zone #04013 NW 56th & W. Holdrege St.

2002 aerial

W. Adams St.

Zoning: R4 to R4Residential Crosss AG Agricultural District

Agricultural Residential District AGR Residential Convervation Clatrica

R/C Office District 0-1

0.2 Suburban Office District

Office Park District

Residential Transition District Local Business District

Planned Neighborhood Dysiness District 0.2

6-3 Commercial District

8-4 Lincoln Center Business District

Planned Regional Business District

Interstate Commercial District

Highway Business District Highway Commercial District

General Commercial District

Industrial Diamics

industrial Park District


Employment Cepter District

Public Use District

One Square Mile Sec. 13 T10N R5E








W. Holdrege St.

Lincoln City - Lencaster County Planning Dept.



LEGAL DESCRIPTION

A part of the North Hair of instruction 13. Township 10 North. Range 5 East of the 6th P.M. Lancaster County. more particularly described as follows:

said extending Corner of said North Half and E. 1320.16 feet to the East Quarter Beginning at the Southeast Corner of thence N 00°00′00′′ E. 1320.16 feet Section 13;

Thence S 89°56'40' W. 390.00 feet:
Thence S 00°00'00' W. 555.80 feet:
Thence N 90°00'00' W. 495.30 feet:
Thence S 00°00'00' W. 190.00 feet:
Thence S 07°22'36' W. 352.88 feet:
Thence S 00°00'17'' E. 224.10 feet:
Thence N 89°59'43'' E. 930.59 feet

feet to the point of beginning ess P containing 20.92 acres. more

SURVEYOR'S CERTIFICATE

direct supervision the State of I hereby certify that this survey was made under my Nebraska, and that

Lyle . Loth. L.S. 314

2-10-2004

LEGAL DESCRIPTION


A part of the North Half of the Southeast Quarter of Section 13. Township 10 North. Range 5 East of the 6th P.M. Lancaster County. More particularly described as follows:

Beginning at the Southeast Corner of said North Half and extending thence N 00°00'00'' E. 1320.16 feet to the East Quarter Corner of said Section 13:

Thence S 89°56'40'' W. 390.00 feet; Thence S 00°00'00'' W. 555.80 feet; Thence N 90°00'00'' W. 495.30 feet; Thence S 00°00'00'' W. 190.00 feet; Thence S 07°22'36'' W. 352.88 feet; Thence S 00°00'17'' E. 224.10 feet;

Thence N 89*59'43'' E. 930.59 feet to the point of beginning containing 20.92 ocres, more or less, except that part already

Zoned R-3.



Memorandum

To:	Becky Horner, Planning Department
From:	Dennis Bartels, Public Works and Utilities Chad Blahak, Public Works and Utilities
Subject:	Hartland's Cardinal Heights 2nd Addition CUP
Date:	February 23, 2004

Engineering Services has reviewed the re-submitted Hartland's Cardinal Heights 2nd Addition CUP, located west of Northwest 56th and south of West Adams Street, and has the following comments:

- According to the grading and drainage plan, portions of the project are to drain to the
 proposed detention cell via a storm sewer system. The pipe sizing calculations shown on
 the grading and drainage plan do not reflect this assumption and should be revised.
- The requested waiver for running sanitary sewer opposite street grade is acceptable as it does not cause the sewer depth to be in excess of design standards. The requested waiver for transferring sewer from one basin to another is acceptable to Public Works as the Waste Water Department has stated that the addition of this plat does not cause capacity problems down stream.



Dennis L Roth

12/01/2003 11:19 PM

To: Rebecca D Homer/Notes@Notes

cc: Subject: re: Hartlands Cardinal Heights, 2nd Add

PROJ NAME: Hartlands Cardinal Heights, 2nd Add, CUP

PROJ NMBR: SP# 2045
PROJ DATE: 11/26/03
PLANNER: Becky Homer

Finding NO duplicate/similar names in our geobase for the street name proposed in this project, other than those which are an extension of an existing street.

Dennis "denny" Roth, ESD II/CAD Admin Emergency Communications 9-1-1 Center

STREETS: NW 56 St, NW 57 St, NW 58 St, W Partridge Ln and W Thatcher Ln

PRIVATE: none

COMMENTS:



Memo

To: Becky Horner, Planning Department

From: Mark Canney, Parks & Recreation

Date: February 20, 2004

Re: Hartland's Cardinal Heights 2nd CUP

Staff members of the Lincoln Parks and Recreation Department have conducted a plan review of the above-referenced application/proposal and the following comments:

- Due to Section 26.23.160 of the Land Subdivision Ordinance, at the City's discretion, the dedication of suitable park land for neighborhood parks as part of the platting process or paying impact fees with the submission of building permits, or a combination of both may be required. The Lincoln Parks Department, at this time is requesting impact fees in lieu of park land dedication.
- All outlot areas to be maintained by the developer and/or future homeowner's association.
- 3. Note the following changes for street tree locations:

NW 58th Street- Autumn Purple Ash

NW 57th Street - Red Sunset Maple

NW 56th Street - Patmore Ash

W. Partridge Lane - Skyline Honeylocust

W. Thatcher - Autumn Blaze Maple

 A final landscape plan does not need to be resubmitted but must accompany the final plat with the above corrections.

If you have any additional questions, comments or concerns, please feel free to contact me at 441-8248. Thank you.



MAYOR COLEEN J. SENG PUBLIC WORKS AND UTILITIES DEPARTMENT

MEMORANDUM

.

 \mathbf{D}_{1}

Fro

Subj

2/20/2004

Becky Homer

Devin Biesecker

Cardinal Heights 2nd

Ben Higgins, Chad Blahak

Below are Watershed Management's comments for Cardinal Heights 2nd four sheet plan set dated February 11, 2004 by the Planning Department.

- 1. Minimum opening elevations are needed for Lots 1,2 and 12-17 on Block 3 adjacent to the detention facility (26.15.020-b-8). The grading on the plat shows the 100 year water surface elevation below most lot elevations but to ensure that individual builders will not significantly change the grading shown on the grading plan minimum opening elevations are needed.
- 2. A geotechnical engineer or a professional geologist must certify that the soil data supplied from the soil survey maps is still appropriate. If the soil survey maps are not appropriate, a subsurface investigation shall be performed and an explanation on how the soil properties will affect the development shall be submitted (26.15.020-e)

INTER-DEPARTMENT COMMUNICATION

-45

DATE:

February 20, 2004

TO:

Becky Horner, City Planning

FROM:


Sharon Theobald

Ext 7640

SUBJECT:

DEDICATED EASEMENTS

DN# 21N-58W



Attached is the C.U.P. for Hartland's Cardinal Heights 2nd Addition.

In reviewing the dedicated transmission line or other electrical easements shown on this plat, LES does not warrant, nor accept responsibility for the accuracy of any such dedicated easements.

ALLTEL, Time Warner Cable, and the Lincoln Electric System will require the additional easements marked in red on the map, along with a blanket utility easement over Outlots B & C.

Sharm Therbald



12/30/2003 11:18 AM

To: R Homer <RHomer@ci.lincoln.ne.us>

CC:

Subject: Cardinal Heights 2nd Addition

Ms. Horner.

The Lincoln Police Department does not object to the Cardinal Heights 2nd Addition CUP and Annex.

Sergeant Michael Woolman Lincoln Police Department

IMPORTANT

Return this report with two sets of corrected plans. The corrections noted below are required to be made to the plans prior to issuance of a permit. Please indicate under each item where the correction is made by plan sheet number or plan detail number.

A seperate set of plans for review and and final approval must be submitted by the licensed installing contractor/s if fire suppression systems, sprinklers, dry powder, fire alarm systems or underground tanks are installed.

Permit # DRF03137

Address

Job Description: Development Review - Fire

Location: CARDINAL HEIGHTS 2ND ADD

Special Permit: **Preliminary Plat: Use Permit:**

2000

CUP/PUD: Y 2045

Requested By: BECKY HORNER

Status of Review: Denied 12/18/2003 12:50:25 PM

Reviewer: FIRE PREVENTION/LIFE SAFETY CODE **BOB FIEDLER**

Comments: need site utility plan showing fire hydrants.

International Building Code and Local Amendments

Current Codes in Use Relating to Construction Development in the City of Lincoln:

2000 International Residential Code and Local Amendments 1994 Nebraska Accessibility Guidelines (Patterned after and similar to ADA guidelines) 1989 Fair Housing Act As Amended Effictive March 12, 1989 1979 Zoning Ordinance of the City of Lincoln as Amended including 1994 Parking Lot Lighting Standards 1992 Lincoln Plumbing Code (The Lincoln Plumbing Code contains basically the 1990 National Standard Plumbing Code and local community Amendments.) 1999 National Electrical Code and Local Amendments

1997 Uniform Mechanical Code and Local Amendments

1994 Lincoln Gas Code

1994 NFPA 101 Life Safety Code

2000 Uniform Fire Code and Local Amendments

Applicable NFPA National Fire Code Standards

Hartland's Cardinal Heights 2nd Original Addition

Estimated impact Fee Equivalent

Using January 1, 2004 Impact Fee Schedule

I:WeWip\HNW2lee.123 Calculated December 19, 2003

				Total Impact Fees				
	Dwelling	Number of Meters		Water System	Water Distribution	Waste- water	Arterial Street	Park &
	Ųniks							
Single Family Detached	31	31	3/4"	\$14,353.00	\$8,897.00	\$11,625.00	\$45,973.00	\$5,983.00
Single Family Detached	15	15	1*	\$11,575.00	\$7,175.00	\$9,375.00	\$22,245.00	\$2,895.00
Single Family Attached	26	26	3/4"	\$12,038.00	\$7,462.00	\$9,750.00	\$20,358.00	\$4,212.00
Multi-Family	<u>o</u>	O O	6"	\$0.00	\$0.00	\$0.00	\$0,00	\$0.00
Dwelling Unit Subtotal	72							
_	Floor Area							
No Commercial Development in Plat	0	0		\$0.00	\$0.00	\$0.00	\$0.00	n/a
	٥	0		\$0.00	\$0.00	\$0.00	\$0.00	n/a
	0	0		\$0.00	\$0.00	\$0.00	\$0.00	n/a
	0	0		\$0.00	\$0.00	\$0.00	\$0.00	n/a
	0	0		\$0.00	\$0.00	\$0.00	\$0.00	n/a
	Ω	0		\$0.00	\$0.00	\$0.00	\$0.00	n/a
Floor Area Subtotal	<u>o</u> o							
TOTAL				\$37,966.00	\$23,534.00	\$30,750.00	\$88,576.00	\$13,090.00

ARTERIAL STREET BY LAND USE CATEGORY

Beginning January 1, 2004

Doyselly Saidley 1, 2004	Unit of	Fee Per
Land Use Time	Measure	Unit
Land Use Type Residential	Measure	Unit
	D	#4 400 00
Single-Family Detached	Dwelling	\$1,483.00
Single-Family Attached /Duplex	Dwelling	\$783.00
Multi-Family	Dwelling	\$903.00
Multi-Family Elderly/ Retirement	Dwalling	\$227.00
Mobile Home	Pad Site	\$814.00
Retall/Commercial		
Shopping Ctr (<100,000 sf)		\$2,178.00
Shopping Ctr (100,000-299,999 sf)		\$1,963.00
Shopping Ctr (300,000-499,999 af)		\$1,894.00
Shopping Ctr (500,000-999,999 sf)		\$1,742.00
Shopping Ctr (1 million sf+)		\$1,685.00
Bank	1000 sq. ft.	\$4,204.00
Convenience Store with Gasoline Sales		\$2,752.00
Movie Theater	1000 sq. ft.	\$1,622.00
Restaurant, Fast Food		\$2,589.00
Restaurant, Sit-Down	1000 sq. ft.	\$2,430.00
Hotel/Motel	Room	\$530.00
Office/institutional		
Office, General	1000 sq. ft.	\$2,178.00
Office, Medical	1000 sq. ft.	\$4,180.00
Hospital	1000 sq. ft.	\$1,048.00
Nursing Home		\$410.00
Church	1000 sq. ft.	\$644.00
Day Care Center	1000 sq. ft.	\$2,702.00
Elementary/Secondary School		\$240.00
Industrial		,
Light Industrial/ Industrial Park	1000 sq. ft.	\$1,338,00
Manufacturing		\$1,073.00
Warehouse		\$758.00
Mini-Warehouse	1000 sq. ft.	
Recreational		, , v
Amusement Park	Acre	\$3,377.00
Bowling Alley		\$3,017.00
Golf Course	Hole	\$2,336.00
Golf Driving Range	Tee	\$1,073.00
Health Club		\$1,831.00
Miniature Golf Course	Hole	\$290.00
THE INCLUSE COLL COURSE	· IONO	4 200.00
I		

WATER SYSTEM FEE PER METER

Degining January 1, 2004				
Motor Size	SFEs/	Fee Per SFE	Fee Per Meter Size	
3/4"	1.00	\$463	\$463.00	
1"	1.67	\$463	\$771.67	
1-1/2"	3.33	\$463	\$1,543.33	
2"	5.33	\$463	\$2,469.33	
3"	10.67	\$463	\$4,938.67	
4"	16.67	\$463	\$7,716.67	
6"	33.33	\$463	\$15,433.33	
18 "	53.33	\$463	\$24,693.33	
10"	76.67	\$4 63	\$35,496.67	

WATER DISTRIBUTION FEE PER METER Beginning January 1, 2004

Degiting Salically 1, 2004				
Meter	\$FE#/	Fee Per	Fee Per	
Size	Meter	SFE	Meter Size	
3/4"	1.00	\$287	\$287.00	
1"	1.67	\$287	\$478.33	
1-1/2"	3.33	\$287	\$956.67	
2"	5.33	\$287	\$1,530.67	
3" 4"	10.67	\$287	\$3,061.33	
4"	16.67	\$287	\$4,783.33	
6"	33.33	\$287	\$9,566.67	
8"	53.33	\$287	\$15,306.67	
10"	76.67	\$287	\$22,003.33	

WASTEWATER FEE PER MEYER Beginning January 1, 2004

	L-OGHIIII Q C	randary 1, 20	
Meter	SFEs/	Fee Per	Fee Per
Size	Meter	SFE	Motor Size
3/4*	1.00	\$375	\$375.00
1"	1.67	\$375	\$625.00
1-1/2"	3.33	\$375	\$1,250.00
2"	5.33	\$375	\$2,000.00
3"	10.67	\$375	\$4,000.00
4"	16.67	\$375	\$6,250.00
6"	33.33	\$375	\$12,500.00
8"	53.33	\$375	\$20,000.00
10"	76.67	\$375	\$28,750.00

NEIGHBORHOOD PARK & TRAIL FEE PER UNIT Beginning January 1, 2004

	Fee Per Unit
Single Family Detached	\$193.00
Single Family Attached	\$162.00
Duplex	\$143.00
Multi-Famiy	\$114.00
Mobile Home (per pad site)	\$164.00